NORDWAVE

Nordwave Engineering & Trading Ltd · 14 Harbour Road, Bristol BS1 6XX
Company no. 11847263 · +44 117 555 0142 · nordwave.example

Commercial offer Q-2611

28 October 2026
Valid for 30 days

CUSTOMER

Tidewater Shipyards B.V.
Procurement, Femke de Vries
Havenstraat 118, 3011 Rotterdam, Netherlands

TERMS

Lead time: 6–7 weeks from down payment
Payment: 50% with order, 50% before shipment
Warranty: 24 months from commissioning

#	Description	Code	Qty	Unit, €	Amount, €
1	Centrifugal pump KP-300/45, duplex 1.4462, 22 kW IE3 motor	KP-300/45-D	40	6,850.00	274,000.00
2	Commissioning supervision (engineer on site, 5 days)	SRV-COM	1	4,800.00	4,800.00
3	Delivery DAP Rotterdam, Tidewater yard	DLV	1	3,900.00	3,900.00

Total (excl. VAT) € 282,700.00

Pump data KP-300/45

Flow / head	120 m³/h at 45 m	Medium	seawater, up to 35 °C
Wetted parts	duplex 1.4462	Shaft seal	mechanical, SiC/SiC
Motor	22 kW IE3, 400 V, 50 Hz	Class approval	DNV

A volume discount for a single shipment of the whole batch can be discussed. We will be glad to answer any questions.

Anna Lindqvist, Head of Sales